



HRAS - PROCUREMENT
REQUEST FOR QUOTATION
Sealed Bidding

PR No.: BPS - 46838

Date: 03/14/2022

R.F.Q. No.: 202203-11103

Delivery 30 days upon signing of contract

Gentleman:

Please quote hereunder your lowest possible price(s) for the following item(s) which is/are urgently needed by this office. It is requested that the quotation be signed, sealed or stamped and submitted to the Supply Section, Ground Floor Department of Trade and Industry, 361 Sen. Gil J. Puyat Avenue, Makati City, Metro Manila.

Table with 5 columns: NO, QUANTITY, UNIT, ARTICLE, UNIT PRICE, TOTAL PRICE. Row 1: 1.0, UNIT, CCTV Supply, delivery and Installation of Fourteen (14) New IP CCTV Camera and Program/Configuration Pulling and line installation for Three (3) Existing IP CCTV Camera. Location: BPS-PTD, CMDF Compound, Dasmarinas City, Cavite. DT: 30 Days. NOTE: Requires site inspection. Please conduct site inspection with the following details:

Remarks All items should be treated as one lot. ABC is Php 380,000.

Prepared by: ILEEN P. VISTA ADMIN OFFICER IV

Very truly yours, MARY ANN D. YULAS SUPERVISING ADMIN. OFFICER

DTI SHOPPING COMMITTEE
Department of Trade and Industry

As per your request, I/We have indicated the prices of the above mentioned articles on the Unit Price and Total Price columns.

Date Submitted

Signature over Printed Name

POSITION:

COMPANY:



HRAS - PROCUREMENT

REQUEST FOR QUOTATION
Sealed Bidding

PR No.: BPS - 46838

Date: 03/14/2022

R.F.Q. No.: 202203-11103

Delivery 30 days upon signing of contract

Gentleman:

Please quote hereunder your lowest possible price(s) for the following item(s) which is/are urgently needed by this office. It is requested that the quotation be signed, sealed or stamped and submitted to the Supply Section, Ground Floor Department of Trade and Industry, 361 Sen. Gil J. Puyat Avenue, Makati City, Metro Manila.

Table with 5 columns: NO, QUANTITY, UNIT, ARTICLE, UNIT PRICE, TOTAL PRICE. The ARTICLE column contains details about the bidding location and contact person.

*****NOTHING FOLLOWS*****

Remarks All items should be treated as one lot. ABC is Php 380,000.

Prepared by: ILEEN P. VISTA ADMIN OFFICER IV

Very truly yours, MARY ANN D. YULAS SUPERVISING ADMIN. OFFICER

DTI SHOPPING COMMITTEE Department of Trade and Industry

As per your request, I/We have indicated the prices of the above mentioned articles on the Unit Price and Total Price columns.

Date Submitted

Signature over Printed Name

POSITION:

COMPANY:

Provision of Services

Supply, delivery and Installation of Fourteen (14) New IP CCTV Camera and Program/Configuration Pulling and line installation for Three (3) Existing IP CCTV Camera

BPS-PTD, CMDF Compound, Dasmarinas City, Cavite

Budget: (380,000.00)

Scope of Works:

- A. Supply and Installation of Cat 6 Cable (Outdoor), RJ-45 Patchcord 24 Port Patchpanel, Wire Manager, 16 Channel NVR, 4 TB Hard Disc, 32 inc TV Monitor, 2 MP Bullet Camera and Dome Camera, HDMI Cable
- B. Supply and Installation of Roughing-ins Plastic Molding Pvc Pipe Square Box, Pull Box and Pittings
- C. Supply and Installation of Hanger and Support Pull Threaded Rod Hecknut w/ Washer, Pipe Clamp, Unistrat Channel and Unistrat Clamp
- D. Cable Pulling and Termination End to End of fourteen (14) UTP Cat 6 Cable Outdoor
- E. Existing Cameras Relocation
 - i. Cable Pulling, Supply, Installation and Configuration End to End of Three (3) Existing CCTV Camera
 - ii. CCTV Monitor HDMI cable extender
- F. Chipping work and Restoration
- G. Painting work and Restoration
- H. Testing and configuration.
- I. As-Built Plan

CCTV MATERIALS	Unit	Lot
UTP Cat6 Outdoor	roll	1
24 Port Patchpanel	Pcs	1
Wire Manager	Pcs	1
4TB Hard Disc	2 Pcs	
16 Chanel w/ PoE	1 Pcs	
2 MP IP Bullet Type Camera	8 Pcs	
2MP IP Dome Type Camera	6 Pcs	
32" LED TV Monitor	1 Pc	
HDMI Cable Extender	2 Pcs	
RJ-45	Pcs	1
ROUGHING-INS MATERIALS 2", Pipe Clamp 3/4", 1", 1 1/4", Pull Box, Unistrat Channel, Unistrat Clamp 3/4", 1", 1 1/4", 1 1/2", 2", Full Threaded Rod 3/8, Heck nut w/ Washer and Grip Anchore PVC Clamp 3/4", 1", 1 1/4", 1 1/2", 2", Square Box, Utility Box, Junction Box Pull Box and Pittings		1
GENERAL REQUIREMENT Miscellaneous and Consumable		1

Mobilization and Demobilization Chipping Work and Restoration		
COMPONENT MATERIALS 24 Port POE switch Series: Gigabit switch with 24 10/100/1000 ports and two SFP fixed 100/1000 Mbps ports. Flexitybility for longer distances with Fiber connectivity using optional SFP transceivers. Fanless. Internal power supply. Ports:(24) RJ-45 autosensing 10/100/1000 ports (2) SFP 100/1000 Mbps ports Supports a maximum of 24 autosensing 10/100/1000 ports plus 2 SFP ports Memory and processor: 1MB flash Packet buffer size: 512 KB Latency: 100 Mb Latency: < 8 ps 1000 Mb Latency: < 16 ps Throughput: up to 38.7 Switching capacity: 52 Gbps Input voltage: 100 - 240 VAC, rated Power consumption: 18 W (maximum)	1	
LABOR Perform Supply, Installation and configuration of UTP Cat 6 Cable Out Door for Installation of seventeen (17) CCTV Camera and Tagging. Testing and As-built Plan		1